

**RECOMMENDATIONS FOR WORK AND FINISHES**

---

- For product stability, painting or laminating both sides of the panel is recommended. Predrilling is required for inserting screws
- 

**RECOMMENDATIONS FOR INSTALLATION**

---

- All panels are approved for interior, non-structural application.

**RECOMMENDATIONS FOR STORAGE**

---

- TRUPAN Standard should never be stored or used outdoors. The indoor storage area should be clean, dry, well-ventilated, and free of dust, dirt or particles that could contaminate the MDF.
  - Store flat on bolsters on a level, hard surface. Constant relative humidity and temperature should be maintained. Before use, allow to stabilize to the same conditions as are expected after the panel is installed Condition 48 to 72 hours prior to lamination.
-